

ZONING CHANGE REVIEW SHEET

CASE: C14-2024-0125 (Stonehollow Tracts East)

DISTRICT: 7

ADDRESS: 11801, 11525 Bldg. A, 11525 Bldg. B, 11525 ½, 11701, 11701 ½, Stonehollow Drive and 2105, 2029 Gracy Farms Lane

ZONING FROM: NBG-NR-NP

TO: NBG-CMU-M-NP

SITE AREA: 28.59 acres

PROPERTY OWNER: TR Stonehollow Corporation (Robert Whitney, Managing Director)

APPLICANT/AGENT: Dubois Bryant & Campbell, LLP (David Hartman)

CASE MANAGER: Sherri Sirwaitis (512-974-3057, sherri.sirwaitis@austintexas.gov)

STAFF RECOMMEDATION:

Staff recommends NBG-CMU-M-NP, North Burnet Gateway- Commercial Mixed Use-Midway Subdistrict-Neighborhood Plan Combining District, zoning.

PLANNING COMMISSION ACTION / RECOMMENDATION:

November 12, 2024: Approved staff's recommendation of NBG-CMU-M-NP zoning by consent (12-0, G. Cox-absent); A. Azhar-1st, D. Skidmore-2nd.

CITY COUNCIL ACTION:

December 12, 2024

ORDINANCE NUMBER:

ISSUES: N/A

CASE MANAGER COMMENTS:

The property in question consists of six tracts of land accounting for 28.59 acres that is currently developed with office/warehouse structures (Stonehollow 1, 2, and 3). It is within the North Burnet/Gateway Combined Neighborhood Planning Area and is located at the southeast intersection of Stonehollow Drive and Gracy Farms Lane (*please see North Burnet/Gateway Neighborhood Plan FLUM – Exhibit D*). The site is zoned NBG with a Neighborhood Residential subdistrict designation: NBG-NR (*please see North Burnet/Gateway Zoning Subdistrict Map – Exhibit E*). To the north, across Gracy Farms Lane, there is a multifamily use (Folio Apartments) zoned NBG-NR-NP. There is a day care facility (The Children’s Courtyard of Austin), a service station/food sales use (7-Eleven Convenience Store) and another multifamily development (The Barstow Apartments-Lincoln Oaks) to the east. The lots to the south and west across Stonehollow Drive, contain office and warehouse uses (Metric Collective, Harmony School of Science) and a recently developed multifamily complex (Modera Eado) zoned NBG-NR-NP.

The applicant is requesting a rezoning in the NBG to a Commercial Mixed Use-Midway subdistrict designation (CMU-M) to permit the redevelopment of this site with more intensive multifamily uses (*Please see Applicant Request Letter – Exhibit C*). The current NBG-NR zoning permits a maximum FAR of 2:1 and up to 60 feet in building height with the development bonus (*Please see Figure 4-1 NR: NBG Zoning District General Site Development Standards – Exhibit F*). The proposed zoning of NBG-CMU-Midway subdistrict will permit a maximum FAR of 10:1 and up to 350 feet in building height with the development bonus (*please see Figure 4-1 CMU: NBG Zoning District General Site Development Standards – Exhibit G*).

The staff’s recommendation is to grant North Burnet/Gateway-Commercial Mixed Use-Midway (CMU-M) District zoning for this property. The conditions and development patterns within the North Burnet/Gateway neighborhood planning area have changed since the regulating plan was adopted, as demonstrated by recent cases including C14-2024-0005 (2700 Gracy Farms) and C14-2024-0090 (11700 Metric). With the rezoning of the property at 11700 Metric to the NMU subdistrict that was approved by City Council on October 24, 2024, this rezoning would establish an upward transition away from Metric and towards the center of the TOD regulating plan. This upzoning is consistent with City Council direction to allow for more intensive development in this area informally referred to as Austin’s “2nd Downtown” near the planned new Capital Metro Broadmoor/Domain rail station on Burnet Road adjacent to the Brandywine Uptown ATX development just north of The Domain and blocks away from Q2 Stadium.

The CMU-Midway subdistrict will encourage a mixture of uses and more density at this location. CMU-M designation will allow for an increase in height and FAR, with the development bonus, toward the northern portion of the North Burnet Gateway Neighborhood Planning area. Across Metric Boulevard, there are multifamily uses that provide a roughly

400' buffer between the edge of the North Burnet/Gateway planning area and the single-family residential neighborhoods to the east.

The site under consideration is located within the North Burnet/Gateway Station Regional Center, as designated by the Imagine Austin Comprehensive Plan. There are Capital Metro bus routes from Gracy Farms Lane to Stonehollow Drive (466-Kramer/Domain) and to the east along Metric Boulevard (routes #142 and #325) and a bus stop to the north on Stonehollow Drive (stop #5760) and to the south at the southwest corner of Metric Boulevard and Stonehollow Drive (stop #2568).

The applicant agrees with the staff's recommendation.

BASIS OF RECOMMENDATION:

1. The proposed zoning should be consistent with the purpose statement of the district sought.

North Burnet/Gateway district is the designation for an identified area of existing low density, auto-oriented commercial, warehouse, and industrial uses that is the subject of an approved master plan for redevelopment of the area into a higher density urban mixed-use neighborhood that is more pedestrian friendly and takes advantage of the links to commuter rail transit and the area's key position in the urban core.

Commercial Mixed Use (CMU) is a high density mixed-use subdistrict, appropriate for high rise residential, major employers, destination retail and large scale civic uses.

Neighborhood Plan district denotes a tract located within the boundaries of an adopted Neighborhood Plan.

2. The proposed zoning should promote consistency and orderly planning.

The CMU-Midway subdistrict will encourage a mixture of uses and more density at this location. CMU-M designation will allow for an increase in height and FAR, with the development bonus, toward the northern portion of the North Burnet Gateway Neighborhood Planning area. Across Metric Boulevard, there are multifamily uses that provide a roughly 400' buffer between the edge of the North Burnet/Gateway planning area and the single-family residential neighborhoods to the east.

3. The proposed zoning should be consistent with the goals and objectives of the City Council.

The property is located within a designated regional center, North Burnet/Gateway Station Regional Center, in the Imagine Austin Comprehensive Plan.

This upzoning is consistent with City Council direction to allow for more intensive development in this area informally referred to as Austin's "2nd Downtown" near the planned new Capital Metro Broadmoor/Domain rail station on Burnet Road adjacent to

the Brandywine Uptown ATX development to the east of The Domain and to the north of Q2 Stadium.

EXISTING ZONING AND LAND USES:

| | ZONING | LAND USES |
|--------------|-----------|---|
| <i>Site</i> | NBG-NR-NP | Office/Warehouse (Stonehollow 1, 2 and 3) |
| <i>North</i> | NBG-NR-NP | Multifamily (Folio Apartments) |
| <i>South</i> | NBG-NR-NP | Office/Warehouse (Metric Collective) |
| <i>East</i> | NBG-NR-NP | Day Care (The Children’s Courtyard of Austin), Service Station/Food Sales (7-Eleven), Multifamily (The Barstow Apartments-Lincoln Oaks) |
| <i>West</i> | NBG-NR-NP | Charter School (Harmony School of Science), Office/Warehouse, Multifamily (Modera Eado) |

NEIGHBORHOOD PLANNING AREA: North Burnet/Gateway NP

NEIGHBORHOOD ORGANIZATIONS:

Austin Independent School District,
 Austin Lost and Found Pets,
 Austin Neighborhoods Council,
 Friends of Austin Neighborhoods,
 Homeless Neighborhood Association,
 Neighborhood Empowerment Foundation,
 North Burnet/Gateway Neighborhood Plan Staff Liaison,
 North Growth Corridor Alliance,
 SELTexas,
 Sierra Club, Austin
 Regional Group

SCHOOLS: Austin Independent School District

Pillow Elementary School
 Burnet Middle School
 Anderson High School

AREA CASE HISTORIES:

| NUMBER | REQUEST | COMMISSION | CITY COUNCIL |
|---|----------------------------|---|--|
| C14-2024-0090 (11700 Metric: 11550 and 11550 1/2 Metric Boulevard) | NBG-NR-NP to NBG-NMU-NP | 9/24/2024: Approved staff’s recommendation of NBG-NMU-NP zoning by consent (10-0, P. Howard, N. Barrera-Ramirez and F. Maxwell-absent); R. Johnson-1st, A. Woods-2nd. | 10/24/24: Approved NBG-NMU-NP zoning by consent on all 3 readings (11-0); J. Velasquez-1 st , N. Harper-Madison-2 nd . |

| | | | |
|--|--|---|---|
| <p>C14-2024-0005 (2700 Gracy Farms: 2700 Gracy Farms Lane and 2700 ½ Gracy Farms Lane)</p> | <p>NBG-NR-NP to NBG-CMU-Midway(CMU-M)-NP</p> | <p>8/13/2024: Approved staff's recommendation of NBG-CMU-M-NP zoning by consent (12-0, P. Howard-absent); A. Azhar-1st, A. Woods-2nd.</p> | <p>9/12/2024: The public hearing was conducted and a motion to close the public hearing and approve Ordinance No. 20240912-105 for North Burnet/Gateway-neighborhood plan (NBG-NP) combining district (commercial mixed use-midway zone subdistrict) zoning was approved on Council Member Vela's motion, Council Member Ellis' second on an 11-0 vote.</p> |
| <p>C14-2021-0173 (11911 Burnet Road)</p> | <p>NBG-NR-NP to NBG-CMU-NP</p> | <p>12/22/21: Approved staff's recommendation of NBG-CMU-NP zoning by consent (8-0); C. Hempel-1st, P. Howard-2nd.</p> | <p>1/27/22: The public hearing was conducted and a motion to close the public hearing and approve Ordinance No. 20220127-082 for NBG-NP combining district (commercial mixed use subdistrict) zoning was approved on Council Member Kitchen's motion, Council Member Fuentes' second on an 11-0 vote.</p> |
| <p>C14-2016-0136 (Broadmoor: 11501 Burnet Road)</p> | <p>NBG-CMU-NP to NBG-TOD-NP</p> | <p>3/27/18: Approved staff's recommendation of NBG-TOD-NP zoning, with conditions, by consent (12-0, P. Seeger-absent); G. Anderson-1st, J. Thompson-2nd.</p> | <p>4/12/18: Approved NBG-TOD-NP zoning, with conditions, on 1st reading only (6-0, G. Casaroff dais, D. Garza, E. Troxclair, K. Tovo and S. Adler-absent); L. Pool-1st, P. Renteria-2nd.</p> <p>6/28/18: Ordinance No. 20180628-088 for north burnet/gateway-transit oriented development-gateway zone-neighborhood plan (NBG-TOD-NP) combining district zoning, with conditions was approved on Council Member Troxclair's motion, Council Member Garza's second on an 11-0 vote.</p> |
| <p>C14-2014-0058 (Esperanza Crossing: 2800 Esperanza Crossing)</p> | <p>NBG-TOD-NP to NBG-CMU-NP</p> | <p>8/12/14: Approved staff's recommendation of NBG-CMU-CO-NP zoning, with conditions, on consent (8-0, B. Roark-absent); S. Oliver-1st, N. Zaragoza-2nd.</p> | <p>8/28/14 : Approved NBG-CO-NP zoning, with conditions, on consent on all 3 readings (7-0); B. Spelman-1st, L. Morrison-2nd.</p> |
| <p>C14-2011-0050 (Burnet-Kramer)</p> | <p>NBG-TOD to NBG-CMU</p> | <p>10/11/11: Approved the staff's recommendation of NBG-CMU-NP zoning for Tract 2,</p> | <p>11/10/11: Approved NBG-CMU-NP zoning with</p> |

| | | | |
|--|--|--|---|
| <p>Rezoning: 11205 & 11301 Burnet Road)</p> | | <p>with the TIA conditions, by consent (9-0); M. Dealey-1st, D. Chimenti-2nd.</p> | <p>conditions on consent on 1st reading only (7-0); Spelman-1st, M. Martinez-2nd.</p> <p>12/08/11: Approved NBG- CMU-NP zoning, with conditions, on consent on 2nd/3rd readings (6-0); C. Riley-1st, S. Cole-2nd.</p> |
| <p>C14-2010-0087 (The Domain Rezoning- Simon)</p> | <p>MI-PDA to MI-PDA</p> | <p>8/24/10: Approved staff's recommendation of MI-PDA zoning (8-1, Chimenti-No), with the following additional conditions: 1) Require the applicant to provide bicycle access for a portion Bicycle Route Segment #905.04 (Please see Public Works Department Memorandum – “Attachment B”) to allow for continuity for bicycle traffic to and through the Domain development. 2) Require a public restrictive covenant that will limit one acre of land on the Endeavor- Domain site to zero percent impervious cover to be signed and recorded before the 3rd reading of this zoning case at City Council.</p> | <p>8/26/10: The public hearing will remain open and the first reading of the case was approved for MI-PDA zoning (7-0); Morrison-1st, Spelman- 2nd, with the following additional conditions: 1) The applicant is to provide bicycle access for a portion of Bicycle Route Segment #905.04 to allow for continuity for bicycle traffic to and through the Domain development. 2) A public restrictive covenant that will limit one acre of land on the Endeavor- Domain site to zero percent impervious cover will be signed and recorded before the third reading of this zoning case.</p> <p>10/14/10: Approved MI-PDA zoning on 2nd/3rd readings (7-0); Spelman-1st, Leffingwell-2nd, with the following amendments: 1) Part 3, C, 1 of the ordinance should read: “A pedestrian/bicycle entrance shall be provided between the existing pedestrian/bicycle trail under Mopac Expressway and the Simon Project internal drive as shown on the attached Exhibit B. A minimum 12-foot wide paved path shall be constructed with an associated curb cut connecting to the internal drive prior to issuance of a certificate of occupancy for a building on Lot 5A, Block A, the Domain Shopping Center Section 3 Subdivision.”; 2) Add</p> |

| | | | |
|---|---------------------------------------|---|--|
| | | | a new paragraph to Part 3, Section D to read: “The two trees on the property numbered 5068 and 5081 as shown on Exhibit D may not be removed, unless the City Arborist approved otherwise based on the health of the individual trees.”; 3) The fourth WHERAS of the restrictive covenant should read: “WHEREAS, the requirements of the Land Development Code for both the Endeavor Tract and the Simon Tract allow for a combined maximum of eighty percent(80%) net site area impervious cover resulting in a total allowable impervious cover area of 135.36 acres for the Endeavor Tract and 40.54 for the Simon Tract. |
| C14-2008-0182 (North Burnet /Gateway NP Rezoning: Metric Boulevard) | Add NP designation to existing zoning | 9/09/08: Approved rezoning of certain tracts to NBG-NP or NBG-H-NP, with conditions (8-0) | 10/16/08: Approved NBG-NP or NBG-H-NP (7-0); 1 st reading 3/12/09: Approved NBG-NP or NBG-H-NP (6-0); 2 nd /3 rd readings |
| C14-2007-0157 (North Burnet /Gateway Neighborhood Plan Rezoning) | | 9/25/07: Approved staff rec. with amendments (8-0) | 10/18/07: Approved 1 st reading of Phase 1 of NP (6-0) 11/01/07: Approved Phase 1 of NP zonings (5-0); 2 nd /3 rd readings |
| C14-2007-0171 (The Domain: 10700-11000 Burnet Road, 11100-11900 Burnet Road, 2800 Block of Braker Lane, 3300 W. Braker Lane) | MI-PDA to MI-PDA | 10/09/07: Approved staff rec. of MI-PDA by consent (9-0) | 11/01/07: Approved MI-PDA zoning on consent (6-0); all 3 readings |
| C14-06-0154 (The Domain: 11400 Burnet Road) | MI-PDA to MI-PDA | 8/08/06: Approved staff rec. of MI-PDA by consent (8-0) | 09/28/06: Approved MI-PDA (7-0); 1 st reading 10/05/06: Approved MI-PDA changes as a condition of zoning (6-0); 2 nd /3 rd readings |

| | | | |
|--|-------------------------|---|--|
| <p>C14-06-0121 (The Domain RCA: 10712, 10728, 10800, 11000, 11500, 11600 Burnet Road; 11601 Domain Drive; 2900, 3001, 3101 Esperanza Crossing)</p> | <p>MI-PDA to MI-PDA</p> | <p>2/13/07: Approved staff's rec. for MI-PDA zoning with additional conditions of:</p> <ul style="list-style-type: none"> • 2 star Green Building rating • natural landscaping of all water quality ponds (existing and future); • be in compliance with TIA conditions; • the applicant's requested parkland dedication proposal; • height base of 140-ft; plus an additional 12-stories based on electing to provide some of the public benefits as listed in the North Burnet/Gateway Neighborhood Plan. • Maximum height of 308 feet. <p>Vote: (9-0); J.Reddy-1st, G. Stegeman-2nd.</p> | <p>3/01/07: Approved MI-PDA zoning with the addition of low albedo roofing materials, one star construction for the total site and two star construction for 50% of the office and residential construction (7-0); McCracken-1st, Dunkerley-2nd.</p> |
| <p>C14-04-0151 (The Domain: 11400 Burnet Road)</p> | <p>MI-PDA to MI-PDA</p> | <p>11/23/04: Approved staff recommendation of MI-PDA, with Environmental Board conditions (9-0).</p> | <p>12/16/04: Approved MI-PDA (7-0); all 3 readings</p> |
| <p>C14-04-0146 (The Shops at Arbor Walk: 10515 North Mopac Expressway)</p> | <p>P to CH</p> | <p>11/9/04: Approved staff's recommendation of CH zoning with conditions (9-0)</p> | <p>12/2/04: Approved CH zoning (7-0); all 3 readings</p> |
| <p>C14-03-0017 (The Domain- 200.286 acres: 11400 Burnet Road)</p> | <p>MI-PDA to MI-PDA</p> | <p>6/11/03: Approved staff's recommendation of MI-PDA zoning, with inclusion of original PDA conditions (as read into the record) from Ordinance #000608-67 (8-0, R. Pratt-off dais)</p> | <p>7/31/03: Granted MI-PDA on all 3 readings (7-0)</p> |
| <p>C14-03-0016 (Multek: 3300 West Braker Lane)</p> | <p>MI to MI-PDA</p> | <p>6/11/03: Approved staff's recommendation of MI-PDA zoning (8-0, R. Pratt-off dais)</p> | <p>7/31/03: Granted MI-PDA on all 3 readings (7-0)</p> |
| <p>C14-03-0015 (The Domain- 0.783 acres:</p> | <p>MI to CS</p> | <p>6/11/03: Approved staff's recommendation of CS-CO zoning (8-0, R. Pratt-off dais)</p> | <p>7/31/03: Granted CS-CO on all 3 readings</p> |

| | | | |
|---|---------------------|---|--|
| 11400 Burnet Road) | | | |
| C14-02-0062 (11005 Burnet Road) | LI to CS-1 | 6/12/02: Approved CS-1 by consent (8-0) | 7/11/02: Approved PC rec. of CS-1 (7-0); all 3 readings |
| C14H-00-2177 (Braker Pointe/ Rogers Homestead: 10801 N. MOPAC NB Expressway | LI-PDA to LI-PDA | 10/24/00: Approved staff rec. of LI-PDA (TR1), LI-PDA-H (TR2) by consent (9-0) | 11/30/00: Approved LI-PDA (TR1) and LI-PDA-H (TR2); (7-0); all 3 readings |
| C14-00-2065 (Austin Tech Park: 11400 Burnet Road) | MI to MI-PDA | 5/9/00: Approved staff rec. of MI-PDA by consent (8-0); with the following conditions: 1) That minimum lot size be 1 acre provided for any lots that directly abut Braker Lane and Burnet Road (but not both) and which are less than 3 acres in size. 2) The total number of additional curb cuts on Braker Lane & Burnet Road providing access to such lots shall not exceed 50 % of the total number of such lots. 3) The foregoing limitation shall not apply to any lot of more than 3 acres, which abut Braker Lane and Burnet Road. | 6/8/00: Approved MI-PDA, with changes agreed to with neighborhood association (7-0); all 3 readings |
| C14-99-0024 (Woodfin Suite Hotel: 2618 Kramer Lane) | MI to GR | 4/20/99: Approved staff alternate rec. of GR-CO, with CO for 2,200 vehicle trip limit, by consent (7-0) | 5/20/99: Approved PC rec. of GR-CO w/ conditions (7-0); 1 st reading 6/3/99: Approved GR-CO w/ conditions (7-0); 2 nd /3 rd readings |

RELATED CASES: C14-2008-0182

OTHER STAFF COMMENTS:

Comprehensive Planning

The subject property located at 11801 Stonehollow Drive is currently developed as warehouse-office on a 28.5-acre site.

The site is nearly adjacent to the CMU zoning district and seeking the CMU-Midway zoning district intended to provide high-density mix of uses including high-rise residential, major employers, destination retail, and large-scale civic uses. The site is adjacent to two existing NBG Pedestrian Priority Collectors shown in Figure 1-3: *NBG Zoning District Roadway Types Map* and Figure 3-12 *NBG Zoning District Collector Street Plan*.

It appears existing zoning capacity established in the NBG Master and Regulating Plans was not ambitious enough to allow the subject property and others like it to respond to market forces which desire to fulfill the intent of the NBG plan through the creation of transit-supportive, higher-density mix of uses. The zoning request appears to be consistent with the intent of the North Burnet Gateway Master Plan as well as urban planning and design best practices primarily by increasing intensity and density of a mix of land uses in the urban core along a transit route within 1 mile of a station for the city's only operational rail line.

NBG Master Plan:

"1. Provide zoning entitlements that allow high density housing developments in the North Burnet/Gateway area (see "Land Use and Zoning" section of this chapter), to increase the supply of housing in Austin and begin to accommodate some of the housing demand that will be generated from expected population growth in the region. 2. Encourage high density housing in close proximity to transit to help reduce vehicle dependency." p94 NBG MP 'Housing'

"1f. Provide for a variety of housing options and affordability, so that people of all income levels can live and work in the area. Encourage housing to be developed in close proximity to potential jobsites as well as public transit so that residents may reduce their dependency on personal vehicles and save on transportation costs." p64 Master Plan Goals

"2a. Create more compact, denser development clustered in activity centers to encourage a greater percentage of travel accomplished by walking, biking, and transit." p64 Master Plan Goals

NBG Regulating Plan:

"General Intent 1.1.6. To allow for and encourage significant higher density residential uses to accommodate some of the region's expected population growth;" p13 NBG RP

"Site Development Standards Intent 4.1.3. Provide opportunities for roadside uses that enliven and enrich the roadway and pedestrian environment, such as outdoor dining, porches, patios, and landscape features;" p56 NBG RP

| 11801 Stonehollow Drive | | |
|---------------------------------|---|---|
| | Current | Request |
| Zoning | NBG-NP Neighborhood Residential (NR) (Figure 1-2) | NBG-NP CMU-Midway (CMU-M) |
| Land Use | Warehouse | Mixed-Use |
| Base Maximum Height | 40 feet (Figure 4-4) | 60 feet |
| Base Maximum FAR | 0.75:1 (Figure 4-2) | 2:1 |
| Development Bonus | Maximum Height: 60 feet (Figure 4-5) Maximum FAR: 1:1 (Figure 4-3) | Maximum Height: 350 feet Maximum FAR: 10:1 |
| Building Setbacks | Interior Side Yard: 0' Rear Yard: 5' | Interior Side Yard: 0' Rear Yard: 0' |
| Maximum Impervious Cover | 60% or maximum allowed by LDC 25-8 (Figure 4-6) | 80% or maximum allowed by LDC 25-8 |
| Compatibility Standards | Yes (Figure 1-6) | Yes |
| Active Edge | N/A (Figure 1-2) | N/A |
| Adjacent Roadway Types | Stonehollow Drive and Gracy Farms Lane are NBG Pedestrian Priority Collector existing streets (Figure 1-3) | Stonehollow Drive and Gracy Farms Lane are NBG Pedestrian Priority Collector existing streets (Figure 1-3) |
| Future Streets | N/A (Figure 1-3) | N/A (Figure 1-3) |

Environmental

The site is not located over the Edwards Aquifer Recharge Zone. The site is in the Walnut Creek Watershed of the Colorado River Basin, which is classified as a Suburban Watershed by Chapter 25-8 of the City's Land Development Code. The site is in the Desired Development Zone.

Under current watershed regulations, development or redevelopment on this site will be subject to the following impervious cover limits:

| <i>Development Classification</i> | <i>% of Gross Site Area</i> | <i>% of Gross Site Area with Transfers</i> |
|--|-----------------------------|--|
| Single-Family (minimum lot size 5750 sq. ft.) | 50% | 60% |
| Other Single-Family or Duplex | 55% | 60% |
| Multifamily | 60% | 70% |
| Commercial | 80% | 90% |

According to floodplain maps there is no floodplain within or adjacent to the project location.

Standard landscaping and tree protection will be required in accordance with LDC 25-2 and 25-8 for all development and/or redevelopment.

At this time, site specific information is unavailable regarding vegetation, areas of steep slope, or other environmental features such as bluffs, springs, canyon rimrock, caves, sinkholes, and wetlands.

Under current watershed regulations, development or redevelopment requires water quality control with increased capture volume and control of the 2-year storm on site.

At this time, no information has been provided as to whether this property has any preexisting approvals that preempt current water quality or Code requirements.

Fire

No comments.

Parks and Recreation

CRITICAL CONNECTION/GREENBELT

Residential units that are certified affordable under the SMART Housing Policy are exempt from the parkland dedication requirements per City Code § 25-1-601(C)(3). Parkland dedication will be required for any new market-rate residential units that may be proposed by this development, at the time of subdivision or site plan application for new residential units, per City Code § 25-1-601, as amended. The proposed development meets the criteria for land dedication in City Code Title 25, Article 14. As such, land dedication will be required, as well as any remaining fees in-lieu.

The site is partially in a park deficient area, defined as being outside walking distance to existing parks. If developed with residential units, parkland dedication will be required for the new residential units. The Parks and Recreation Department (PARD) would consider a neighborhood park and/or multiple midblock greenbelt connections (not roads). The parkland would go toward satisfying the requirement at time of permitting (whether subdivision or site plan). Should there be any remaining fees in-lieu, those fees shall be used toward park investments in the form of land acquisition and/or park amenities within the

surrounding area, per the Parkland Dedication Operating Procedures § 14.3.11 and City Code § 25-1-609.

Should the applicant wish to discuss parkland dedication requirements in advance of site plan or subdivision applications, please contact this reviewer: ann.desanctis@austintexas.gov. At the applicant's request, PARD can provide an early determination letter of the requirements as stated in this review.

Site Plan

Site plans will be required for any new development other than single-family or duplex residential.

Any new development is subject to Subchapter E. Design Standards and Mixed Use. Additional comments will be made when the site plan is submitted.

This tract is already developed, and the proposed zoning change is a footprint within the existing development.

FYI this tract is in the North Burnet neighborhood planning area.

Transportation

Zoning transportation analysis shall be performed at zoning where anticipated trips are anticipated to exceed 2,000 unadjusted trips to satisfy the LDC requirement for a TIA but does not diminish the authority to require a traffic impact analysis at site plan. LDC 25-6, TCM 10.5.0.

The Austin Strategic Mobility Plan (ASMP) calls for 116 feet of right-of-way for Stonehollow Dr. It is recommended that 58 feet of right-of-way from the existing centerline should be dedicated for Stonehollow Dr according to the Transportation Plan with the first subdivision or site plan application. [LDC 25-6-51 and 25-6-55].

The Austin Strategic Mobility Plan (ASMP) calls for 116 feet of right-of-way for Gracy Farms Ln. It is recommended that 58 feet of right-of-way from the existing centerline should be dedicated for Gracy Farms Lane according to the Transportation Plan with the first subdivision or site plan application. [LDC 25-6-51 and 25-6-55].

The adjacent street characteristics table is provided below:

| Name | ASMP Classification | ASMP Required ROW | Existing ROW | Existing Pavement | Sidewalks | Bicycle Route | Capital Metro (within ¼ mile) |
|-------------------|----------------------------|--------------------------|---------------------|--------------------------|------------------|----------------------|--------------------------------------|
| Stonehollow Drive | Level 3 | 116 feet | Approx 82 feet | Approx 57 feet | Yes | Yes | Yes |
| Gracy Farms Ln | Level 3 | 116 | Approx 80 feet | Approx 45 | Yes | Yes | Yes |

Water Utility


No comments on zoning change.

FYI: The landowner intends to serve the site with existing City of Austin water utilities.

Depending on the development plans submitted, water and or wastewater service extension requests may be required. All water and wastewater construction must be inspected by the City of Austin. For more information pertaining to the Service Extension Request process and submittal requirements contact the Austin Water SER team at ser@austintexas.gov.




INDEX OF EXHIBITS TO FOLLOW

- A: Zoning Map
- B. Aerial Map
- C. Applicant’s Request Letter
- D. North Burnet/Gateway Neighborhood Plan FLUM
- E. North Burnet/Gateway Zoning Subdistrict Map
- F. Figure 4-1 NR: NBG Zoning District General Site Development Standards
- G. Figure 4-1 CMU: NBG Zoning District General Site Development Standards
- H. Zoning Traffic Analysis for Cases C14-2024-0125 & C14-2024-0126



ZONING

ZONING CASE#: C14-2024-0125


-  SUBJECT TRACT
-  PENDING CASE
-  ZONING BOUNDARY

1" = 400'





This product is for informational purposes and may not have been prepared for or be suitable for legal, engineering, or surveying purposes. It does not represent an on-the-ground survey and represents only the approximate relative location of property boundaries.

This product has been produced by the Planning Department for the sole purpose of geographic reference. No warranty is made by the City of Austin regarding specific accuracy or completeness.





Stonehollow Tracts (East)

-  SUBJECT TRACT ZONING CASE#: C14-2024-0125
-  ZONING BOUNDARY LOCATION: 11801, 11525 Bldg. A, 11525 Bldg. B, 11525 ½, 11701, 11701 ½ Stonehollow Dr. 2105, 2029 Gracy Farms Ln.
-  PENDING CASE SUBJECT AREA: 28.59 Acres
-  CREEK BUFFER MANAGER: Sherri Sirwaitis





August 15, 2024

Lauren Middleton-Pratt
Director, Planning Department
City of Austin
1000 E. 11th Street, Suite 200
Austin, Texas 78702

Re: Stonehollow Tracts Zoning and NPA Applications - Rezoning Application for 28.59 acres at 11801, 11525 Bldg. A, 11525 Bldg. B, 11525 ½, 11701, 11701 ½, Stonehollow Dr, and 2029 and 2105 Gracy Farms Ln. (“Stonehollow Tracts East”); Rezoning Application for 9.35 acres at 11800, 11800 ½, 11700, 11700 ½ Stonehollow Dr. (“Stonehollow Tracts West”); Neighborhood Plan Application (“NPA”) covering the Stonehollow Tracts East and Stonehollow Tracts West.

Dear Ms. Middleton-Pratt:

We respectfully submit the enclosed rezoning applications for the above stated Stonehollow Tracts East (“Zoning Application East”) and Stonehollow Tracts West (“Zoning Application West”, together the Zoning Application East and Zoning Application West, being collectively referred to as the “Zoning Applications”) as representatives of the property owners. The tracts that comprise the Stonehollow Tracts East and Stonehollow Tracts West covered by the Zoning Applications and the related NPA are identified in the attached Exhibit “A”.

The Stonehollow Tracts East and Stonehollow Tracts West (together the Stonehollow Tracts East and Stonehollow Tracts West, being collectively referred to as the “Property”) are currently zoned NBG-NR-NP (North Burnet/Gateway – Neighborhood Residential Subdistrict - Neighborhood Plan), with a subdistrict designation of Neighborhood Residential (NR). The Zoning Applications seek to rezone the Property from NBG-NR-NP to NBG-CMU-M (Midway Zone)-NP (North Burnet/Gateway-Commercial Mixed Use-Midway Subdistrict-Neighborhood Plan), with a subdistrict designation of CMU-M (Midway Zone) Subdistrict. Adjacent zoning includes NBG-NP zoning with the following subdistricts: Transit-Oriented Development – Gateway Zone (TOD-Gateway Zone) Subdistrict, Transit-Oriented Development – Midway (TOD-Midway) Subdistrict, and CMU (Commercial Mixed-Use) Subdistrict. The proposed CMU-M (Midway Zone) Subdistrict authorizes redevelopment of the Property for transit-oriented development, including much-needed housing (including affordable housing) in this area identified in the Imagine Austin Comprehensive Plan as the North Burnet/Gateway Regional Center and Austin’s “second downtown.”

The Property is located within the North Burnet/Gateway Neighborhood Planning Area. This Neighborhood Plan designates the Property as Mixed Use on the Future Land Use Map (“FLUM”). A Neighborhood Plan Amendment application covering the Property is filed in conjunction with the Zoning Applications to change the FLUM from Mixed Use to High Density Mixed Use.

The Property is located at Stonehollow and Gracy Farms Lane, and near Metric Blvd. and Burnet Road with robust multimodal connectivity. The Property is located within ½ mile of the proposed Capital Metro Red Line Broadmoor Station commuter rail station, and is near multiple bus stops/routes along Stonehollow Dr. and Metric Boulevard. Stonehollow Dr., Gracy Farms Ln., and Metric Blvd. are ASMP Level 3 Streets. Burnet Rd. is an Imagine Austin Corridor, an ASMP Level 3 Street, an ASMP Transit Priority Network street, and a Core Transit Corridor.

A Zoning Traffic Analysis is required per the enclosed TIA Determination Worksheet signed by Ramin Komeili, P.E., on 8/12/24.

If you have any questions about the application or need additional information, please do not hesitate to contact me at your convenience. Thank you for your time and attention to this project.

Very truly yours,





David Hartman

cc: Joi Harden, Planning Department (via electronic delivery)
Maureen Meredith, Planning Department (via electronic delivery)



Property Profile

Exhibit "A"



Legend

Appraisal Districts

TCAD Parcels

Zoning 1

Zoning Text

Zoning 2


Regulating Plan Subdistrict


- NBG Commercial Mixed Use
- NBG Neighborhood Mixed Use
- NBG Neighborhood Residential
- Transit Oriented Development

Notes

This product is for informational purposes and may not have been prepared for or be suitable for legal, engineering, or surveying purposes. It does not represent an on-the-ground survey. This product has been produced by the City of Austin for the sole purpose of geographic reference. No warranty is made by the City of Austin regarding specific accuracy or completeness.

Page 19 of 26





**North Burnet-Gateway
Combined Neighborhood Planning Area
Future Land Use Map (FLUM)**

Future Land Use Categories

- Mixed Use
- High Density Mixed Use
- Industry
- Civic
- Recreation & Open Space

Figure 1 - 2 : North Burnet / Gateway (NBG) Zoning District Subdistrict Map

Revised 08-04-22

LEGEND

NBG Subdistricts :

 Transit - Oriented Development (TOD / TOD Midway)

 TOD - Gateway Zone

 Commercial Mixed - Use (CMU)

 CMU - Midway Zone

 CMU - Gateway Zone

 Neighborhood Mixed Use (NMU)

 Neighborhood Residential (NR)

 Warehouse Mixed Use (WMU)


 Commercial Industrial (CI)

 Active Edges

 NBG Planning Area Boundary

 Parcel Boundary

 Railroads



City of Austin
 Council Meeting Agenda
 FIGURE 4-1 NR ZONING DISTRICT GENERAL SITE DEVELOPMENT STANDARDS
NEIGHBORHOOD RESIDENTIAL (NR) SUBDISTRICT

| LOT SIZE | |
|-------------------|----------|
| Minimum Lot Size | 1,600 SF |
| Minimum Lot Width | 20 Feet |

| MINIMUM SETBACKS | |
|---|--------|
| Front Yard and Street Side Yard*: | |
| No ground-level front yard or street side yard setbacks are required. Instead, development must meet the building placement standards in Section 4.3. | |
| Front and Street Side Upper-Story Building Facade Stepbacks: | |
| The building facade at the 6th story and above must be stepped back 30 feet from the ground-level building facade line. | |
| Interior Side Yard: | 0 Feet |
| Rear Yard: | 5 Feet |
| * If the street right-of-way is less than 60 feet in width, the minimum front yard setback for buildings three or more stories in height shall be 30 feet from the center line of the street to ensure fire access. | |

| MAXIMUM IMPERVIOUS COVER | |
|--|-----|
| If located in an urban watershed (Shoal or Little Walnut Creek) : | |
| Established on Figure 4-6 (Based on the maximum impervious cover allowed by the property's zoning prior to adoption of the this Document.) | |
| If located in a suburban watershed (Walnut Creek)*: | 60% |
| * This requirement supersedes impervious cover requirements of Section 25-8-394(C) of the LDC. | |

| FLOOR TO AREA RATIO | |
|---|-----|
| Maximum Floor-to-Area Ratio (FAR) by Right: | |
| Established on Figure 4-2 (Based on the maximum FAR allowed by the property's zoning prior to adoption of this Document) | |
| Maximum Floor-to-Area Ratio (FAR) with Development Bonus: | 2:1 |
| This FAR may be granted in exchange for the provision of public benefits. The development bonus criteria and standards are detailed in Article 6. | |

| BUILDING HEIGHT* | |
|---|---------|
| Minimum Building Height: | |
| Not applicable | |
| Maximum Building Height by Right: | |
| Established on Figure 4-4 (Based on the maximum height allowed by the property's zoning prior to adoption of this Document.) | |
| Maximum Building Height with Development Bonus: | 60 Feet |
| This building height may be granted in exchange for the provision of public benefits. The development bonus criteria and standards are detailed in Article 6. | |
| * Properties may be required to comply with the building height restrictions in Subsection 4.2.10 Compatibility Standards, if triggered by a property outside of the NBG Planning Area. | |



Typical examples of buildings in the Neighborhood Residential Subdistrict.




FIGURE 4 - 1 CMU : NBG ZONING DISTRICT GENERAL SITE DEVELOPMENT STANDARDS
COMMERCIAL MIXED USE (CMU) SUBDISTRICT

Exhibit "B"

Revised 08-04-22

| LOT SIZE | |
|-------------------|----------|
| Minimum Lot Size | 2,500 SF |
| Minimum Lot Width | 20 Feet |

| MINIMUM SETBACKS | |
|---|--------|
| Front Yard and Street Side Yard*: | |
| No ground-level front yard or street side yard setbacks are required. Instead, development must meet the building placement standards in Section 4.3. | |
| Front and Street Side Upper-Story Building Facade Stepbacks: | |
| The building facade at the 6th story and above must be stepped back 30 feet from the ground level building facade line. | |
| Interior Side Yard: | 0 Feet |
| Rear Yard: | 0 Feet |
| * If the street right-of-way is less than 60 feet in width, the minimum front yard setback for buildings three or more stories in height shall be 30 feet from the center line of the street to ensure fire access. | |

| FLOOR TO AREA RATIO | |
|---|------|
| Maximum Floor-to-Area Ratio (FAR) by Right: | |
| Established on Figure 4-2 (Based on the maximum FAR allowed by the property's zoning prior to adoption of this Document) | |
| Maximum Floor-to-Area Ratio (FAR) with Development Bonus: | |
| CMU Zone | 3:1 |
| CMU Midway Zone | 10:1 |
| CMU Gateway Zone | 12:1 |
| This FAR may be granted in exchange for the provision of public benefits. The development bonus criteria and standards are detailed in Article 6. | |




| BUILDING HEIGHT | |
|---|----------|
| Minimum Building Height: | |
| Not applicable | |
| Maximum Building Height by Right: | |
| Established on Figure 4-4 (Based on the maximum height allowed by the property's zoning prior to adoption of this Document.) | |
| Maximum Building Height with Development Bonus*: | |
| CMU Zone | 180 Feet |
| CMU Midway Zone | 350 Feet |
| CMU Gateway Zone | 420 Feet |
| This building height may be granted in exchange for the provision of public benefits. The development bonus criteria and standards are detailed in Article 6. | |
| *Exception: If adjacent to or across the street from NR Subdistrict the maximum height is 120 feet. | |

| MAXIMUM IMPERVIOUS COVER | |
|--|--|
| If located in an urban watershed (Shoal or Little Walnut Creek) : | |
| Established on Figure 4-6 (Based on the maximum impervious cover allowed by the property's zoning prior to adoption of this Document.) | |
| If located in a suburban watershed (Walnut Creek)*: 80% | |
| * This requirement supersedes impervious cover requirements of Section 25-8-394(C) of the LDC. | |

Typical examples of buildings in the Commercial Mixed Use Subdistrict.

| PLATTING REQUIREMENTS | |
|---|--|
| If located in the CMU Gateway Zone: | |
| Section 24-4-171 (Access to Lots) of the City Code is modified to permit a lot to abut a dedicated public street or a Major Internal Drive. | |





MEMORANDUM

From: Austin Jones, P.E.
To: Kelly Rees, P.E.
CC: Renee Johns, AICP; Ramin Komeili, P.E.

Date: September 18, 2024
Subject: Stonehollow Multifamily – Zoning Transportation Analysis Final Memo (C14-2024-0125, C14-2024-0126)

The Transportation & Public Works Department (TPW) has reviewed the September 12th, 2024, “Stonehollow Multifamily Zoning Transportation Analysis”, prepared by Kimley-Horn. The proposal is for a new mid-rise multifamily development consisting of 1,585 dwelling units. The site is located south of Gracy Farms Ln and west of Metric Blvd in the City of Austin, Texas.

The site will have access to the surrounding roadway network via three driveways on Gracy Farms Ln and eight driveways on Stonehollow Dr. The proposed driveways will be situated at the same location as the existing driveways that are currently in use for accessing the existing development. The development is anticipated to be constructed in one phase to be completed in 2027.




Figure 1. Site Location

Roadways

Gracy Farm Lane

The ASMP classifies Gracy Farm Ln. as 4 travel lanes with a raised median (Level 3) roadway in the vicinity of the site. According to TxDOT average daily traffic counts, the 2020 ADT was approximately 4,922 vehicles per day (vpd). The posted speed limit is 35 mph. ASMP recommends improvements to include constructing additional travel lanes, raised medians, and all ages and abilities bicycle facilities. ROW dedication may be required from new development and commercial redevelopment through the land development process. Required ROW does not apply to single-family home properties.

Stonehollow Dr

The ASMP classifies Gracy Farm Ln. as 4 travel lanes with a raised median (Level 3) roadway in the vicinity of the site. The posted speed limit is 35 mph. ASMP recommends improvements that include adding a raised median, consolidating driveways, and all ages and abilities bicycle facilities. ROW dedication may be required from new development and commercial redevelopment through the land development process. Required ROW does not apply to single-family home properties.

Trip Generation and Traffic Analysis

The project assumes 1,585 high-rise multi-family dwelling units (ITE Code 222). Based on the Institute of Transportation Engineer's Trip Generation Manual, 11th Edition, the proposed development will generate 7,196 vehicle trips per day. See **Table 1** for a detailed breakdown of the trip generation.

Table 1. Trip Generation

| Land Use | Size | Trip Generation (Daily) |
|--------------------------------------|----------------------|-------------------------|
| 222 - Multifamily Housing (Mid Rise) | 1,585 Dwelling Units | 7,196 |
| Total Unadjusted Trips | | 7,196 |
| <i>Existing Trips</i> | | 2,372 |
| <i>TDM Trips (10% Reduction)</i> | | 720 |
| TOTAL ADJUSTED TRIPS | | 4,104 |

The existing trips were obtained from tube count data, then site trips were added to these volumes using an estimate of the traffic distribution to and from the proposed site. **Table 2** shows both the existing traffic volumes as well as projected volumes on each road in the vicinity of the site.

Table 2. Added Traffic

| Street | Existing Traffic [vpd] | Proposed New Site Traffic to each Roadway | Overall Traffic (Existing + Site) [vpd] | Typical ADT Range |
|------------------------|------------------------|---|---|-------------------|
| Gracy Farm Lane | 5,659 | 1,295 | 6,954 | 10,000-20,000 |
| Stonehollow Dr (North) | 2,280 | 1,619 | 3,899 | 10,000-20,000 |
| Stonehollow Dr (South) | 2,416 | 3,562 | 5,978 | 10,000-20,000 |

Recommendations/Conclusions

As a condition for approval for the above referenced zoning review case, the applicant shall adhere to the following requirements:

1. The applicant has committed to achieving a trip reduction of 10% through Travel Demand Management (TDM). TDM measures and a sustainable modes analysis will be provided during the Site Plan review process.
2. The City of Austin reserves the right to reevaluate any or all identified improvements associated with this case at the time of Site Plan review.
3. The ASMP ROW requirements have been assessed, and the site may require ROW dedications to meet ASMP standards. This will be confirmed during the Site Plan phase.
4. Street Impact Fee (SIF) Ordinances [20201220-061](#) and [20201210-062](#) have been adopted by City Council and are effective as of December 21, 2020. The City has started collecting street impact fees with all building permits issued on or after June 21, 2022. For more information, please visit the City's [Street Impact Fee](#) website. A Street Impact Fee calculation shall be performed at the time of the Site Plan submission to be collected at the time of building permit.
5. All construction items should be designed and incorporated into the site plan, and all street impact fees should be paid in full. No offsets to the proposed development's SIF will be issued until completion of all identified construction items unless those items are included in the proposed Site Plan application.
6. This ZTA does not relieve a development of its Transportation Assessment or Full TIA requirement at time of site plan.
7. This ZTA does not grant nor guarantee approval of proposed driveway types or locations. Driveway types and locations will be reviewed with the site plan application.

Please contact me at austin.jones2@austintexas.gov or (512)-978-1671 if you have questions or require additional information.



Austin Jones, P.E.

Transportation Public Works Department, City of Austin